

Name of the work: Fixing of chequerred tiles in front of old power engineering shed in
CMERI, Durgapur

ESTIMATE

Item No.	Particulars of items	Unit	Qty	Rate (Rs.)	Amount (Rs.)
1	Providing & fixing of designer Chequerred precast cement concrete tiles of 25 mm thick in footpath & courtyard, jointed with neat cement slurry (@ 4.4 kg/Sq.m at back side of tiles) mixed with necessary pigments to match the shade of tiles, including rubbing and cleaning etc. complete, on 20 mm thick bed of cement mortar 1:4 (1 cement: 4 coarse sand). Design & colour of Chequerred tiles (conforming to the scheduled specifications) shall be approved by EIC.	cum Sq.m	250.00		
2	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 & Cement mortar 1:6 (1 cement : 6 coarse sand) in foundation and plinth.	cum	1.00		
3	12 mm cement plaster of mix of mix 1:4 (1 cement : 4 fine sand).	Sqm	20.00		
			Total		

Total Rs. (in words)

Shadia
12/01/18